



GVD Contracts Ltd
Widney Church
Widney Road, Bentley Heath
Solihull B93 9BN
Tel: 01564 783299
 E: info@gvdcontracts.com
 W: www.gvdcontracts.com

Edward Peel
 4 Victoria Road
 Harborne
BY EMAIL

23rd March 2026

Re: Extension & Retaining Wall

	WORKS	£
1.	Project management, including building control inspections etc	£10,000.00
2.	Mobilise site, welfare, temporary fencing etc.	£1,000.00
3.	Temporarily protect driveway, internal access passage way. Lift and dispose of existing hardstanding patio areas, remove vegetation to boundary, remove brick boundary wall to neighbouring property.	£2,450.00
4.	Excavate and lay concrete foundations for extension, opening to existing house, and retaining wall/steps	£5,260.00
5.	Install underground drainage to extension, and land drains behind retaining wall.	£2,200.00
6.	Build new concrete block retaining wall and steps, structural engineer specification required for wall. Infill brickwork/blockwork to existing doorway opening leading to patio area	£6,950.00
7.	Extension structure up to DPC, Raise levels for flush threshold patio	£3,800.00
8.	Install insulated solid concrete floor structure ready for screed finish	£4,200.00
9.	Install pre-fabricated steel frame for glazed elevation, and supporting steels to opening between existing house and extension.	PSUM £6,500.00
10.	Brick and block walls to new extension, bricks to match existing house.	£8,900.00
11.	Roof structure, vaulted internally, glazed rooflight to pitch against house.	£6,500.00
12.	Aluminium Cladding finish to glazed elevation	PSUM £3,000.00
13.	Form new downstairs WC and install new drainage connection.	£3,050.00
14.	First fix electrics to standard spec	£3,000.00
15.	First fix heating to standard spec	£3,000.00
16.	Plasterboard and skim all new walls and disturbed areas to existing house.	£7,000.00
17.	Remove all waste and debris	£3,000.00
	Sub Total	£79,810.00
	VAT	£15,962.00
	Total Cost	£95,772.00
	NOTES –	

Yours sincerely

Jordan Smith

Jordan Smith
Director